BRUHAT BANGALORE MAHANAGARA PALIKE

O/o, Executive Engineer (MPED-C), N.R.Square, BBMP, Bengaluru-560002

No. E.E/MPED(C)/QTN/02/2025-26
Date:14.08.2025

SHORT TERM QUOTATION NOTIFICATION FOR RATES

Quotation is invited from the reputed agencies / Suppliers / Distributors /Contractors for the following items The interested supplier/agencies are requested to submit/upload their quotation **through KPP-Portal** on or before **22.08.2025 at 5:30 pm** as detail in the table indicated below, the quotation shall be opened on **25.08.2025 at 10:30 pm.**

Sl.	Particulars	Unit	Qty
A	**TREATMENT FOR DAMPNESS IN STEM WALL FOR DOME**		
1	**Surface preparation work:** Removing of existing debonded/delaminated lime plaster by gentle chipping, as per specification and cleaning the surface with air and water jet /sand blasting as directed by the Engineer-in-charge.Cost is inclusive of all materials, labours, macheniery, equipement and all other incidental charges with all lead & lift, scaffolding, loading & unloading etc complete.	Sqm	1.0
2	**Lime based cement free coloured, pure natural hydraulic lime and Eco-pozzolon based masnory:** Providing **20-25mm** thick lime based mortar covering the entire surface of the stem wall as per direction of Engineer-in-charge. Cost is inclusive of all materials, labours, macheniery, equipement and all other incidental charges with all lead & lift, scaffolding, loading & unloading etc complete.	Sqm	1.0
B	**TREATMENT FOR DETERIORATED LIME MORTAR**		

Sl.	Particulars	Unit	Qty
	JOINTS IN SIZE STONE MASNORY DOME		
1	**Surface preparation work:** Removing of existing eoroded/cracks etc in motar joints by gentle chipping, as per specification and cleaning the surface of dome shall be carriedout with air and water jet to remove dust as directed by the Engineer-in-charge.Cost is inclusive of all materials, labours, macheniery, equipement and all other incidental charges with all lead & lift, scaffolding, loading & unloading etc complete.	Rmt	1.0
2	**Drilling of holes & fixing PVC nozzles:** Providing 10 mm dia holes, 75mm to 100mm deep drilled in the leaky/damp locations of size stone masonry joints for fixing PVC nozzles as detailed in sketch and cleaning of holes with air and water jet.as per direction of Engineer-in-charge. Cost is inclusive of material, labour,equipement scaffolding tools and tackles, consumables etc complete.	Nos	1.0
3	**Lime based slurry grouting:** Providing nozzles grouting carried out using salt resistant, fillerized hydraulic binder based on lime and Eco-pozzolan, chemical grout until refusal with pressure not less than 5-6 psi and directions of Engineer-in-charge. COST inclusive of all materials,equipments hire charges,consumables,labour, lead and lift, tools and tackles etc. complete.	Kgs	1.0
C	**COLORLESS WATER REPELLENT PROTECTION AGAINST RAIN FOR SIZE STONE MASONRY**		
1	**Surface preparation Dome:1 to 8** Removing dust, oil & efflorosence etc. on the surafce of the dome masonry by brushing with suitable detergents or by light air blast cleaning or steam cleaning etc as directed by the Engineer-in-charge.COST inclusive of all materials ,labour,consumables,staging, lead and lift, tools and tackles etc.,complete.	Sqm	1.0
2	**Siloxane based water repellent:** Application of Siloxane based water repellent carried out as per specification and directions of Enginner-in-charge. COST inclusive of all materials,equipments hire charges,consumables,labour, lead and lift, tools	Sqm	1.0

Sl.	Particulars	Unit	Qty
	and tackles etc. complete.		
D	**WATER PROOFING TERATMENT FOR ROOF SLAB**		
1	**Surface preparation** Removing dust, oil & efflorosence etc. on the surafce of the existing slab by brushing with suitable detergents or by light air blast cleaning or steam cleaning etc as directed by the Engineer-in-charge.COST inclusive of all materials ,labour,consumables,staging, lead and lift, tools and tackles	Sqm	1.0
2	**Installation of Reinforced TPO Memberane:** Providing and installing reinforced TPO 1.5 mm membrane as per the specifications and as directed by the Engineer-in-charge.COST inclusive of all materials ,labour,consumables,staging, lead and lift, tools and tackles etc.,complete.	Sqm	1.0
3	**50mm thick screed mortar with waterproofing chemical:** Providing and laying 50mm thick screed mortar with 1:4 ratio with waterproofing chemical upon the TPO membrane as illustarated in the sketch and as directed by the Engineer-in-charge. COST inclusive of all materials ,labour,consumables,staging, lead and lift, tools and tackles etc.,complete.	Sqm	1.0

TERMS AND CONDITIONS:

1. The agency shall quote the rate as per the specification and drawing prescribed.
2. The rate quoted shall be inclusive of all materials, labour, fabrication, transportation etc…, excluding GST
3. The quotations are invited for the purpose of budgetary offer for adopting rates in the estimate.
4. The agencies do not have any claim for entrustment of work.
5. Any other information shall be had from the office of the under signed during office hours or **Contact No.8892124229**
6. BBMP reserves right to accept or reject the quotation part or all without assigning any reasons.

-sd/-
Executive Engineer (MPED-C)
Bruhath Bangalore
Mahanagara Palike

COPY SUBMITTED TO:-

1. Personnel Secretary to Hon'ble Administrator to bring into the kind notice of the Hon'ble Administrator.
2. Personnel assistant to Hon'ble Commissioner for kind information.
3. Special Commissioner (Projects)/ Special Commissioner (Finance) for kind information
4. Engineer – in – Chief for kind information.
5. Chief Engineer (Project-Central) for kind information.
6. CAO / Chief Auditor for kind information.
7. I. T. Advisor with a Request to publish the same in the BBMP Website.
8. Public Relation Officer, BBMP for information and to publish in two leading National Newspapers in Kannada and English.
9. Notice board & Office Copy.

Executive Engineer
MPED-CENTRAL
Bruhat Bangalore Mahanagara
Palike